

## LIST OF CORRECTIONS

<b>Chart</b>	105
	Kanaal Gent - Terneuzen
	Edition April 2019
<b>Updated up to and including NMs</b>	20 / 2020
	24 September 2020

The last version of these corrections are available on [www.flemishhydrography.be](http://www.flemishhydrography.be)

### **2019**

07/113 - 08/126(T) - 09/142(T) - 10/147 - 10/151 - 11/171(T) - 11/177(T) - 17/236 - 19/252(T) - 20/253 - 22/278(T) - 24/300(T) - 25/308

### **2020**

02/085 - 02/086 - 04/117(T) - 06/133 - 09/173(T) - 10/182 - 10/202 - 17/269(T) - 20/293

**2019**

**2019-07/113 CANAL GHENT-TERNEUZEN - GHENT SEA PORT - DREDGING BELGIAN PART CANCELLED**

NtM 2018-23/263(T) is cancelled.

**2019-08/126(T) CANAL GHENT-TERNEUZEN - ZELZATE - WORKS ARCELOR MITTAL**

Hydraulic engineering work is being carried out for the construction of the All Weather Terminal at quays 5435-5450-5465-5480.

The works will last until 31 December 2019.

There is a general mooring prohibition in the working area for all shipping with the exception of shipping intended for or engaged in this work.

Shipping must avoid waves from 100 m before and up to 100 m after the working area.

The start of the working area is indicated with the following signs:

- A9 Prohibited to cause annoying water movement
- B8 Mandatory to pay particular attention
- C5 (95m) (direction Z-N) the waterway is at a certain distance (95m) from the shore.

The end of the working area is indicated with the following signs:

- E11 End of a prohibition or order applies to one direction.

**2019-09/142(T) CANAL GHENT-TERNEUZEN - MOERVAART - WORKS**

Due to works along the southern bank of the Moervaart between the bridge of the R4 and the corner of the canal Gent-Terneuzen, the vessels sailing in and out the Moervaart, have to pass with caution and to remain at a distance of 15 m of the existing wall.

The works will probably last until the end of September 2019.

**2019-10/147 GENERAL NOTICES - NEW PUBLICATION - CHART 105**

New edition of 2019 of the:

Belgian chart 105

Kanaal van Gent naar Terneuzen

Chart 105 - edition 2019 is available from now in the Webshop for the amount of 25 euro.

For more information about the purchase of this chart, consult

[www.vlaamsehydrografie.be](http://www.vlaamsehydrografie.be) > Publications > Webshop.

**2019-10/151 CANAL GHENT-TERNEUZEN - ZELZATE - WORKS QUAYS 5345-5405 ENDED**

NtM 2018-21/243(T) is cancelled.

## **2019-11/171(T) CANAL GHENT-TERNEUZEN - BELGIAN PART - DREDGING OPERATIONS**

Dredging operations are performed on the Belgian part of Canal Ghent-Terneuzen. The works are taking place at the edges of the main channel.

The works are carried out from the pontoon "DN40" which remains in position by means of spud poles. The pontoon can be moved within 15 minutes if it is necessary for shipping.

The works will last until the end of August 2019, from Monday 7 a.m. until Saturday 7 a.m. During the weekend and on holidays, there are no works.

Further information is available at Uitkijk Zelzate +32 9 358 5160 and/or Havendienst Gent +32 9 251 5639.

## **2019-11/177(T) CANAL GHENT-TERNEUZEN - TERNEUZEN - MIDDENSLUIS - WORKS IN PROGRESS**

There are works in progress near Middensluis, Terneuzen. A temporary access channel has been created, the Rooiboskanaal, for the accessibility of the Middensluis. This channel is only for barges.

Chart an area "works in progress" in positions:

- 51°20,03'N	003°49,00'E
- 51°20,05'N	003°49,11'E
- 51°19,98'N	003°49,16'E
- 51°19,96'N	003°49,20'E
- 51°19,96'N	003°49,25'E
- 51°19,85'N	003°49,30'E
- 51°19,81'N	003°49,09'E

## **2019-17/236 CANAL GHENT-TERNEUZEN - TERNEUZEN - WEST BUITENHAVEN - LIGHTS - CORRECTION OF CHARTS AND LIST OF LIGHTS**

Insert lights F.Y with range 1 NM, on the following locations:

Pile 2	in position 51°20,24'N	003°48,49'E	(Int. no. B0249.5 - nat. no. 0685.1)
Pile 4	in position 51°20,17'N	003°48,55'E	(Int. no. B0249.8 - nat. no. 0685.2)
Pile 6	in position 51°20,09'N	003°48,61'E	(Int. no. B0250.3 - nat. no. 0685.3)
Mooring pile 13	in position 51°20,06'N	003°48,66'E	(Int. no. B0250.7 - nat. no. 0685.4)
Mooring pile 23	in position 51°19,94'N	003°48,76'E	(Int. no. B0250.9 - nat. no. 0685.5)

## **2019-19/252(T) CANAL GHENT-TERNEUZEN - TERNEUZEN - ROOIBOSKANAAL - CHANGE OF BUOYAGE**

Insert:

Green spar buoy "RB 1", Iso.G.2s, in position 51°19,98'N 003°49,07'E

Move:

East cardinal buoy "NST 1-O", Q(3)10s,	to position 51°19,64'N 003°49,35'E
East cardinal buoy "NST 2-O", Q(3)10s,	to position 51°19,57'N 003°49,37'E

## **2019-20/253 CANAL GHENT-TERNEUZEN - BELGIAN PART - DREDGING OPERATIONS CANCELLED**

NtM 2019-11/171(T) is cancelled.

**2019-22/278(T) WESTERN SCHELDT - TERNEUZEN - WORKS CONSTRUCTION "NIEUWE SLUIS TERNEUZEN"**

Due to the construction of the new lock "Nieuwe Sluis Terneuzen" multiple works are in progress until 2022.

**2019-24/300(T) CANAL GHENT-TERNEUZEN - TERNEUZEN - NIEUWE SLUIS - WORKS IN PROGRESS EXTENDED**

NtM 2019-11/177(T) is cancelled.

The works in progress near "Middensluis Terneuzen" are extended. A temporary access channel has been created, the Rooiboskanaal, for the accessibility of the Middensluis. This channel is only for barges.

Chart an area "works in progress" in positions:

- 51°20,03'N 003°49,00'E
- 51°20,05'N 003°49,11'E
- 51°19,98'N 003°49,16'E
- 51°19,96'N 003°49,20'E
- 51°19,96'N 003°49,25'E
- 51°19,85'N 003°49,30'E
- 51°19,54'N 003°49,48'E
- 51°19,50'N 003°49,38'E
- 51°19,76'N 003°49,12'E

**2019-25/308 CANAL GHENT-TERNEUZEN - TERNEUZEN - NEW LOCK - CHART CORRECTION**

NtM 2019-19/252(T) is cancelled.

Insert accompanying blocks.

Pay attention to the scale when printing, see printer settings.

**2020**

**2020-02/085 CANAL GHENT-TERNEUZEN - MOERVAART - WORKS IN PROGRESS  
CANCELLED**

NtM 2018-08/106(T) is cancelled.

**2020-02/086 CANAL GHENT-TERNEUZEN - MOERVAART - WORKS IN PROGRESS  
CANCELLED**

NtM 2019-09/142(T) is cancelled.

**2020-04/117(T) WESTERN SCHELDT - HONTE - PAS VAN TERNEUZEN - INSTRUMENTS**

Insert following instruments:

MP2 51°26,78'N 003°39,79'E - unmarked

MP3 51°24,51'N 003°42,38'E - marked with yellow conical buoy with rare

MP4 51°20,67'N 003°48,73'E - unmarked

The duration of the measurement is approximately 1 month, the measurement frames are expected to be picked up again in week 10.

**2020-06/133 CANAL GHENT-TERNEUZEN - TERNEUZEN - DELETE WORKS IN PROGRESS**

NtM 2019-24/300(T) is cancelled.

**2020-09/173(T) CANAL GHENT-TERNEUZEN - SAS VAN GENT - WORKS IN PROGRESS**

There are works in progress at the Westkade Sas van Gent near the company "Rosier".

The works will last until 30 January 2021, longer or shorter in duration depending on the progress of the works.

The shipping is asked to pass the works with necessary caution to avoid making waves.

**2020-10/182 CANAL GHENT-TERNEUZEN - ZELZATE - WORKS ARCELOR MITTAL  
CANCELLED**

NtM 2019-08/126(T) is cancelled.

**2020-10/202 WESTERN SCHELDT - HONTE - PAS VAN TERNEUZEN - MEASUREMENTS ENDED**

NtM 2020-04/117(T) is cancelled.

**2020-17/269(T) CANAL GHENT-TERNEUZEN - SLUISKIL - AXELSE VLAKTEHAVEN - WORKING AREA QUAY YARA**

There is a working area in the HAS harbour (Axelse Vlaktehaven) at quay Yara from mooring post 18 up to mooring post 36 up to and including 50m from the quay. Mooring prohibition and prohibited sailing for all shipping except work and government vessels.

The works will last until 2 October 2020.

The shipping is requested to pass the works with necessary caution and avoid waves.

Further details will be announced via "Scheepvaartberichten" on Marifoonkanaal 11 and can be obtained from the Terneuzen Traffic Control Centre by telephone 088-7980501.

**2020-20/293 CANAL GHENT-TERNEUZEN - TERNEUZEN - WORKS NEW LOCK TERNEUZEN**

NtM 2019-22/278(T) is cancelled.